



CENTRAL EVERGLADES PLANNING PROJECT



Governing Board Update

Tom Teets,
Office of Everglades
Policy and Coordination

March 15, 2012



CERP COMPONENTS UNDER
CONSIDERATION

CENTRAL EVERGLADES PLANNING PROJECT

NEPA SCOPING TOPICS-COMMENTS


- Water Quality Requirements
- Water Quality and Quantity Assumptions
- Savings Clause Analyses
- Use of Existing SFWMD Lands
- Modified Water Deliveries
- Project Features
- Use of Adaptive Management
- Multi-Species Approach
- Ecosystem Services Benefit Analysis
- Expedited Planning Process
- Seepage Control
- Lake Okeechobee Regulation Schedule
- Incorporation of ASR
- Recreation
- Incorporation of “new” science
- Modeling & Evaluation Tools
- Trade-offs
- Water Levels in WCA-3A
- Decompartmentalization of WCA-3A
- Bridging

GOALS AND OBJECTIVES

- **GOAL: Enhance Ecological Values**
- **Improve habitat and functional quality**
 - ▶ Restore seasonal hydroperiods and freshwater distribution to support a natural mosaic of wetland and upland habitat in the Everglades system
 - ▶ Improve sheetflow patterns and surface water depths and durations in the Everglades system in order to reduce soil subsidence, the frequency of damaging peat fires, the decline of tree islands, and salt water intrusion
 - ▶ Reduce high volume discharges from Lake Okeechobee to improve the quality of oyster and SAV habitat in the northern estuaries
- **Improve native plant and animal species abundance and diversity**
 - ▶ Reduce water loss out of the natural system to promote appropriate dry season recession rates for wildlife utilization
 - ▶ Restore more natural water level responses to rainfall to promote plant and animal diversity and habitat function
- **GOAL: Enhance Economic Values and Social Well Being**
- **Increase availability of fresh water (agriculture/municipal/industrial)**

CENTRAL EVERGLADES PROCESS

TARGET - 18 MONTHS



IPR: In-Progress Review with Corps Leadership

ANALYSIS PHASE

- **Project Delivery Team- March 1**

- Draft Project Management Plan (Scope & Schedule Document)
- Developed Draft Plan Formulation Strategy
- Initial Screening of Management Measures
- Initial Screening of Lands in EAA for Siting Features
- Modeling Assumptions for Existing and Future Without Project Condition
- Next PDT Meetings– March 26

- **Working Group Sponsored Public Workshops**

- 2-Day Science Workshop (February 13-14)
- Recreation Workshop (north of I-75) (March 1)
- EAA Workshop-Configuration Development Exercise (March 9)
- Recreation Workshop – south (April 17)

SCIENCE COORDINATION GROUP (SCG) PUBLIC WORKSHOP ON SCIENCE FEBRUARY 13 and 14




SCG SPONSORED PUBLIC WORKSHOP ON SCIENCE

- More than 170 participants, ~90 in person, and ~80 viewed the live webcast
- Participants included the public, NGOs, public officials, agency staff, consultants, managers, scientists, and engineers
- 30-min presentations, 30-min discussions
- No shortage of questions and discussion

SCG SPONSORED WORKSHOP ON SCIENCE

“What We Heard”

- A sense of urgency, but not despair
- Current declines can be mitigated or reversed
- Significant new science since 2000 that is relevant to CEPP (wetter Everglades, greater flows, targets, and super colonies)
- There are new and improved tools, particularly models
- A practical focus on what this next increment can accomplish



***Prioritize restoration
in areas that are
most in peril, but
that have high
potential to respond
to increased flows***



The most effective way to preserve high functioning ridge-slough will be through careful water depth management with pulsed flow releases that maximize water surface slope for weeks per year.

Larsen, Harvey, and Crimaldi, *Ecological Engineering*, 2009

NEW TOOLS


Model Comparison

- **NSM 9,000 mi²**
 - 2328 2x2 mile grid cells
- **SFWMM 7,000 mi²**
 - 1,746 2x2 mile grid cells
- **NSRSM 12,000 mi²**
 - 7,438 Triangular (variable mesh) cells ranging 0.75 miles per side to 5.5 miles per side




CENTRAL EVERGLADES

- Restoration objectives for the Lake and the estuaries are consistent with those for the Greater Everglades
- A practical focus on what this next increment can accomplish




WORKING GROUP SPONSORED RECREATION WORKSHOP

Northern Portion of Central Everglades




HYDROPATTERN RESTORATION



4 sections with new pump stations to redistribute inflows

- Western: degrade L-4 Levee from S-8 to L-28 (3.3 miles)
- Mid-western: spreader canal parallel to L-5 Levee (3.5 miles)
- Mid – spreader canal parallel to L-5 Levee (8.5 miles)
- Eastern – gap “remnant” L-5 (5 miles; 1000’ gaps at 0.5 mile intervals) 14

MIAMI CANAL SEGMENTS





WORKING GROUP SPONSORED WORKSHOP

March 9

- Project Feature Siting Analysis
- Feature Type Trade-Offs
- Configuration Development Exercise
- Existing Conditions Performance
- Screening Framework

CONFIGURATION DEVELOPMENT EXERCISE




**CENTRAL EVERGLADES
 Planning Project
 Base Map**
 S.F.W.M.D. OWNED EAA LANDS

sfwmd.gov
 South Florida Water Management District
 6515 SECTION 10, ROAD 10, PALM BEACH, FL 33411
 888.484.8800 • 561.833.1100 • 561.833.1101 • www.sfwmd.gov
 HAWAII ADDRESS: 100, Kono Place, Kailua-Kona, HI 96740





For copies of the map base, please contact the Planning Project Manager, Central Everglades Planning Project, South Florida Water Management District, 6515 Section 10, Road 10, Palm Beach, FL 33411.

EXISTING CONDITIONS




EXISTING CONDITIONS






PLAN FORMULATION AND EVALUATION STRATEGY

CEPP PLAN FORMULATION FRAMEWORK




INITIAL SCREENING



CEPP


QUANTITY & QUALITY



Management Measures



- Shallow storage
- Deep storage
- Storm Water Treatment Areas
- Aquifer Storage & Recovery
- Improved conveyance
- Operations

Management measures for Quantity/Quality will be formulated to reduce high volume discharges from the Lake and restore seasonal hydroperiods and freshwater distribution in the Everglades system.




CEPP

CONVEYANCE & DISTRIBUTION



Management Measures



- Canal plugs & backfill
- Spoil mound removal
- Spreader canals
- Levee removal, gaps
- Gated water control structures, culverts, weirs
- Bridging
- Collector canal
- Operations



Management measures in the WCAs and ENP will be formulated to meet objectives for distribution and conveyance (location, direction, depths, volume, and/or timing) of the available water.

CEPP

SEEPAGE MANAGEMENT



Management Measures

- Detention areas
- Seepage collection canals & pumps
- Raise canal stages
- Flood attenuation reservoir
- Re-locate existing canals or pump stations
- In-ground barriers



Management measures are necessary to control seepage along the eastern side of WCA-3B and ENP, retaining water in the natural system while satisfying the planning constraint for flood risk management.

NEXT STEPS

Task

Completion

Initial Management Measures
Screening

April 1, 2012

Component optimization and
alternative development


August 30, 2012

Evaluate final array of alternatives
and select preliminary TSP

October 30, 2012

Formal Letter of Support
by Governing Board

March /April 2013



QUESTIONS?